



*Nova Bus Flooring Replacement*

*Statement of Work*

*June 8, 2017*

Santa Barbara Metropolitan Transit District  
550 Olive Street • Santa Barbara, CA 93101  
Phone: (805) 963-3364 • Fax: (805) 963-3365 • Website: [www.sbmtd.gov](http://www.sbmtd.gov)

# ***SANTA BARBARA METROPOLITAN TRANSIT DISTRICT***

## **Invitation for Bids for Nova Bus Flooring Replacement**

### ***STATEMENT OF WORK***

#### **Project Description**

Santa Barbara Metropolitan Transit District (MTD) is soliciting bids to replace the Altro floor covering in seven 1998 40-ft. Nova buses. The work is to include replacement of floor covering and repair of bus subfloors as needed. Qualifying bidders shall have verified experience installing Altro floors in transit buses and verified experience repairing wood sub floors in transit buses.

#### **Options**

In addition to the seven buses in the base project as described above, MTD may require replacement of Altro floor covering in up to seven additional 1998 40-ft. Nova buses. MTD will determine whether to exercise one or more of the options within 60 days of the notice to proceed.

#### **Work to be Performed**

- Two color samples of Altro flooring are to be provided to MTD by the successful bidder. One sample shall be accepted by the MTD Project Manager as material approval prior to commencement of work, and one shall be retained by MTD.
- Contractor must provide a secure workspace and must transport the buses to and from the MTD bus yard. The cost of transporting buses shall be included in the overall bid.
- Provide all flooring materials, glue, weld strip, trim and miscellaneous material to install flooring in MTD Nova 40-ft. buses. The floor material is to be ALTRO Midnight 2.7 Meta.
- Remove passenger seats, stanchions, driver's seat, wheelchair restraints, and modesty panels as required to perform work.
- Remove all worn Altro floor material, standee lines, nosing, and required floor trim.
- Inspect plywood sub-floor to determine if rot or delamination of plywood sub-floor exists and to what extent repairs to sub-floors are needed. Contractor shall inform the MTD Project Manager of needed repairs and shall provide written quote of additional work in accordance with the pricing indicated on the Price Bid form prior to proceeding with repairs.
- In the event repair of sub-floor is required and the MTD Project Manager is unable to visit the project site, a photo log of requisite repairs, by bus number, shall be emailed to the MTD Project Manager.
- Sand, level, and prep the plywood subfloor prior to installation of Altro flooring.
- Cut new Altro flooring, standee lines, and nosing to fit. Glue all flooring, standee lines, door nosing, and sub-floor. Weld and seal all seams and caulk all edges. Replace all damaged floor trim as required.
- Install passenger seats, stanchions, driver's seat, wheelchair restraints, and modesty panels.
- Clean interior of bus upon completion of work.

#### **Schedule**

- All work shall be completed by September 15, 2017 to minimize the impact on MTD bus service. Each bus shall be returned to MTD with all work completed within seven calendar days after leaving MTD.

- Contractor shall supply proposed work schedule with bid.

### **Acceptance**

- Each completed bus must be signed off by MTD prior to MTD providing another bus to Contractor.

### **Warranty**

- Contractor shall guarantee their workmanship for a period of five (5) years. This warranty will cover, but not be limited to, delaminating of floor from subfloor, cracking of floor material, splitting at welded seams of the new flooring material and all repairs of bus subfloors made by Contractor.
- Contractor shall pass-through the standard floor-covering warranty from Altro. Any failure of floor material during this standard warranty period will be repaired at no charge by Contractor.